Abstract estimate for constructing Middle School at Gundlupet.
Compound wall at rear of Building.

Sl. No	Particulars of work	No.	Dimensions	Remarks
1	Earthwork excavation	C yds.	11	
2	Concrete foundation one foot deep	C.ft.	99	
3	Stone mortar foundation 2' deep	,,	199	
4	Stone in clay basement	,,	143	
5	Burnt brick in clay superstructure	,,	283	
6	Burnt stone slabs dressed and fixed	S.ft.	18	
7	Plastering complete with chunam one coat rubbed with trowel, complete	Sqr.	6·79	
8	Whitewashing as per plastering	,,	6·79	
9	Cement pointing basement	,,	1·72	
10	Burnt brick in chunam with coping studded with glass pieces over.	R.ft.	58	
11	Wrought iron gate way with iron wheels, etc., painting, complete.	S.ft.	52	

N. G. KRISHNA IYENGAR,
Executive Engineer.

SHIMOGA DIVISION.

Notice dated 18th December 1928.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Shimoga Division, up to 15th January 1929, for constructing a Musafirkhana at Chandragutty, Sorab Taluk. An approximate estimate of quantities is given below These quantities are not guaranteed. The work should be completed by the end of June 1929.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Shimoga, between the hours of 11 A.M. to 5 P.M. on the office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

Description of work	Unit of work	Rate per unit

4. Each tender must be accompanied by a deposit of Rs. 250 in cash or Government Promissory Notes, as earnest money and be superscribed "Tender for constructing a Musafirkhana at Chandragutty, Sorab Taluk," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, Shimoga Circle, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate of quantities for constructing a Musafirkhana at Chandragutti in Sorab Taluk.

No.	Items of work	Unit	Quantity
1	Earthwork excavations for foundations	C.yds.	58
2	Size stone in mortar	C.ft.	3,075
3	Burnt brick in clay	,,	2,309
4	Burnt brick in chunam	,,	343
5	Burnt stone slabs 6" thick dressed and fixed	Sq. ft.	204
6	Teakwood doors battened	,,	72
7	Teakwood windows with iron bars, etc., complete	,,	30
8	Honneywood work wrought and put up	C.ft.	105·08
9	Roofing with first class Mangalore tiles on teak reepers ...	Sqr.	17·97
10	Mangalore ridge tiles set in mortar	R.ft.	192
11	Ventilating tiles	Each	14
12	Plastering with chunam	Sqr.	30·84
13	White and colour washing	,,	50·84
14	Pointing with chunam	,,	6·38
15	Flooring with Cudapah slabs on 3" concrete bed with cement pointing	,,	8·26
16	Providing zinc sheets for valleys over teakwood planks ...	R.ft.	50
17	Tarring to wood work	Lump	sum
18	Chocolate painting to doors and windows	Sqr.	2·04
19	Providing and fixing teakwood gate with iron fittings ...	Sq. ft.	48
20	Coping with chunam to the walls at sides of gate	R.ft.	7
21	Clearing site	Lump	sum
22	Providing a mortar and a pestle	Each	1

M. A. SRINIVASACHARI,
Executive Engineer.

MISCELLANEOUS DEPARTMENTS.

OFFICE OF THE EXCISE COMMISSIONER IN MYSORE, BANGALORE.

TENDER FOR STITCHING UNIFOM CLOTHING.

Memo No. C1-918-28, *dated* 19*th December* 1928.

1. Sealed tenders will be received in the Office of the Excise Commissioner in Mysore-New Public Offices, Bangalore, up to 12 noon on the 15th January 19 29, for the stitching of uniform clothing of the specifications noted below, required for the use of the Sub-Inspec. tors and Tree-markers of the department.

2. The approximate number of suits required is given in the statement annexed and tenders should be sent in the form of that statement duly noting in the column left blank, the quantity of cloth required and the rate at which each suit will be stitched. The suits should be stitched in three sizes.

3. The whole number of suits should be delivered within 3 (three) months from the date of acceptance of the tender.

4. A deposit of Rs. 50 should accompany every tender, without which the tenders will not be considered.

5. Final acceptance of the tender will rest with the Excise Commissioner who does not bind himself to accept the lowest or any tender or to assign any reason what so ever for the rejection of any tender.

6. The deposit amount of the successful tenderer will be held as a security for the due fulfilment of the contract on his execution of an agreement to that effect and earnest money of rejected tender will be returned.

7. The successful tenderer will be required to execute an agreement within ten days from the date of communication of the acceptance of his tender to him, failing which the deposit will be forfeited to Government.